

New Jersey



▲ NJPDES Wastewater Facilities



D1 - Aunt Kitty's Foods, Inc. [NJ098914]
D6 - Landis Sewerage Authority [NJ0025364]
D8 - Marcacci Meats LLC [NJ0065544]
D9 - Mid Atlantic Recycling Technologies, Inc. [NJ0147559]
D11 - Rural Development Corporation [NJG0082147]

Text Notes for Map No. 2:

- All existing, new or expanded industrial pretreatment facilities requiring Significant Indirect User (SIU) permits and/or Treatment Works Approvals, and which are located within the specified sewer service area, are deemed to be consistent.
- Individual subsurface sewage disposal systems (ISSDS) for individual residences can only be constructed in depicted sewer service areas if legally enforceable guarantees are provided, before such construction, that use of such systems will be discontinued when the depicted sewer service becomes available. Connection of properties to the sewer system is required under §585-5 of the Code of the City of Vineland. This applies to ISSDS that require certification from the Department under the Ready Improvement Sewerage and Facilities Act (N.J.S.A. 58:12-23) or individual Treatment Works Approval or New Jersey Pollutant Discharge Elimination System Permits (under N.J.A.C. 7:14A). It also applies to ISSDS which require only local approvals if the WMP acknowledges adequate arrangements for enforcement of the requirement (such as through a municipal or sewerage authority ordinance).
- Development in areas mapped as wetlands, flood prone areas, designated river areas, or other environmentally sensitive areas may be subject to special regulation under Federal or State statutes or rules. Interested persons should check with the Department of Environmental Protection for the latest information. Depiction of environmental features is for general information purposes only and shall not be construed to define the legal geographic jurisdiction of such statutes or rules.
- For facilities (including but not limited to sewer connections, sewer extensions and onsite treatment plants) which are located in the Pinelands Area, as defined in N.J.S.A. 13:18A-11, the approval of the Pinelands Commission pursuant to the requirements of the Pinelands Comprehensive Management Plan (CMP) is required prior to construction. All facilities and activities included within this WMP should be consistent with the requirements of the CMP.
- Locations of future pump stations, major interceptors and trunk sewers are being provided for general information only and will not serve as the basis for any future consistency determinations or permit reviews unless the pump station, major interceptor or trunk sewer is part of a State or federally funded project.
- Pursuant to N.J.A.C. 7:15, Riparian zones are: 300 feet from top of bank (or centerline of a first order stream where no bank is apparent) for waters designated as Category One and all upstream tributaries within the same HUC 14; 150 feet from waters designated Trout Production and all upstream waters; 150 feet for water designated Trout A; maintenance and all upstream waters within one linear mile as measured along the length of the regulated water; 150 feet for any segments of water flowing through an area that contains documented habitat for a threatened or endangered species of plant or animal, which is critically dependent on the surface water body for survival; and all upstream waters (including tributaries) within one linear mile as measured along the length of the surface water body; 150 feet for waters that run through acid-producing soils; and; 50 feet for all waters not designated as C1, trout waters, critically water dependent Threatened and/or Endangered Species Habitat, or associated with acid soils.

Surface waters designations are listed in the Surface Water Quality Standards at N.J.A.C. 7:9B. The Department's "Surface Water Quality Standards" GIS data layer was utilized to determine these waters. The applicable buffers have been applied to these waterways and removed from undeveloped subdivisible lots within the proposed sewer service areas on the mapping.

- Notes:
- BASE MAPS - BUENA, NEWFIELD, FIVEPOINTS, AND MILLVILLE 1:24,000 USGS QUADRANGLE MAPS.
 - CURRENT WMP AREA CONSISTS OF THE CITY OF VINELAND, B&B POULTRY CO. INC. IN PITTSBURGH TWP., SALEM CO., CUMBERLAND COUNTY COLLEGE IN THE CITY OF MILLVILLE, AND MEREDITH FARMS CORP. IN FRANKLIN TWP., GLOUCESTER CO.
 - LSA SEWER DISTRICT CONSISTS OF THE CITY OF VINELAND.
 - ENTIRE PLANNING AREA IS IN THE MAURICE RIVER DRAINAGE BASIN.
 - NEW JERSEY STATE PLANE FEET, DATUM NAD83



- | | |
|---|--------------------------------|
| Restricted Septic Service Area ⁽¹⁾ | Protected Open Space |
| NJPDES Service Area | Empowerment |
| LSA WWTP | Rural Development Zone |
| LSA Future Sewer Service Area | Non-Discharge Area (Pinelands) |
| Milville Future Sewer Service Area | Vineland City |
| WMP Planning Area | |

⁽¹⁾ Restricted Septic Service Area is restricted to planning flows of 2,000 gpd or less and less than 6 residential units

WASTEWATER MANAGEMENT PLAN FUTURE WASTEWATER FACILITIES MAP #2

May 2011
LANDIS SEWERAGE AUTHORITY
Cumberland County, New Jersey

Prepared By:
CET Engineering Services, 1240 North Mountain Road, Harrisburg, PA 17112
Copyright © 2011 by Commonwealth Engineering & Technology, Inc. T/A CET Engineering Services. All Rights Reserved.